Item No.	Description of work	Per	Rate	Quantity	Rate to be offered
			Rs. a. p.		
6	Grade stones with figuring and painting, etc., complete	No.	1 4 0	50	
7	Index stones do	„	0 6 0	50	
8	Register No. and date stone cutting figures and painting	„	3 0 0	1	
9	B. M. Stones	„	2 8 0	2	
10	Gauge stones do	„	15 0 0	1	
11	Jungle clearing, removing ant-hills and filling sand and cutting grips, etc.	Grade	5 0 0	50	
	Weir at 50.00.				
1	Earthwork excavation and using the same to bund	C.yds.	0 3 6	529	
2	Stone jelly concrete in surki mortar	C.ft.	0 4 0	1,395	
3	Burnt brick in surki mortar	„	0 4 0	3,561	
4	Nice surki mortar plastering	Sqrs.	3 8 0	8.63	
5	Burnt stone slabs 6″ thick dressed	S.ft.	0 4 6	1,400	
6	Rough stone apron with jelly backing and wedging	C.yds.	1 8 0	322	
7	Joggle joints	Each	1 0 0	42	
	Sluice No. 1 *at* 44.00.				
1	Earthwork cutting bund	C.yds.	0 3 0	28	
2	Refilling with watering and tamping	„	0 2 0	31	
3	Stone jelly concrete in surki mortar	C.ft.	0 4 0	341	
4	Burnt brick in surki mortar	„	0 4 0	267	
5	Burnt stone slabs 6″ thick dressed	S.ft.	0 4 6	257	
6	Plastering with surki mortar and rendering with cement	Sqr.	6 0 0	4·01	
7	Cutting orifice in slabs	Each	1 0 0	4	
	Sluice No. 2 *as per sluice No.* 1.				
1	Earthwork cutting bund	C.yds.	0 3 0	28	
2	Refilling with watering and tamping	C.yd.	0 2 0	31	
3	Stone jelly concrete in surki mortar	C.ft.	0 4 0	341	
4	Burnt brick in surki mortar	„	0 4 0	267	
5	Burnt stone slabs 6″ thick dressed	S.ft.	0 4 6	257	
6	Plastering with surki mortar and rendering with cement	Sqr.	6 0 0	4.01	
7	Cutting orifice in slabs	S.yd.	1 0 0	4	

C. R. IYENGAR,
Executive Engineer.

SHIMOGA DIVISION.

Abstract Notification dated 18th November 1939.

CONSTRUCTING A GIRDER BRIDGE WITH 12′ ROAD WIDTH ACROSS THE RIVER DANDAVATI IN SORAB TALUK (5/6 OF SORAB-ANAVATTI ROAD).

The attention of the public is hereby invited to the advertisement in pages 2356-2358, Part VI of the *Mysore Gazette*, dated 23rd November 1939, calling for tenders for constructing a girder bridge with 12′ road width across the River Dandavati in Sorab Taluk (5/6 of Sorab-Anavatti Road).

Each tender must be accompanied by a Treasury challan for having deposited Rs. 1,500 as earnest money.

The last date for receiving tenders is 11th December 1939 up to 4 P.M.

Notification dated 28th November 1939.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 3 P.M., on 22nd December 1939, for improving Sri Lakshminarasimhaswami Temple at Bhadravati. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1940.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga, between the hours of 11 A.M. and 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer on payment of annas four only. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a Treasury chellan for Rs. 285, as earnest money, and be superscribed "Tender for improving Sri Lakshminarasimhaswami Temple at Bhadravati," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. The successful candidate will be required to deposit an another sum of Rs. 285 towards the security deposit. This will be withheld from Bills.

14. Chamundy brand cement should be used for cement works.

15. The teak wood should be purchased from Government Depots.

Abstract estimate for improvements to Sri Lakshminarasimhaswamy Temple at Bhadravati.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
1	Removing the existing coping slabs over the compound wall and refixing them at a higher level in mortar	S.ft.	0 2 0	550	
2	Size stone in mud to raise the compound wall by 2', left side, etc.	C.ft.	0 4 0	1,098	
3	Dismantling the existing ugly brick wall at the southern side and removing the debris	,,	0 0 3	525	
4	Dismantling the bits of compound wall on either side of the existing pakasala and yagasala in front and stacking the materials after starting	,,	0 0 6	103	
5	Constructing a new compound wall as per design of the existing compound raised by 2 more feet in size stones in mud	R.ft.	4 6 0	565	
6	Earthwork excavation for the platform in front of the temple to the level of approach road and conveying the earth to fill up low ground in the surroundings	C.yds.	0 3 0	744	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
7	Concealing the suspended electric lamps from view	L. S.	..	..	
8	Providing electric poles and lamps round the prakara	No.	30 0 0	5	
9	Providing two (2′×2′×9′) stone masonry gate pillars including foundations	Each	20 0 0	2	
10	Providing and fixing a C. I. gate 12′×6′ including fixing arrangements, painting, etc., complete	S.ft.	2 8 0	72	
	Constructing Quarters for Archaka of Sri Lakshminarasimhaswamy Temple.				
1	Earthwork excavating foundations and filling in basements, tamping, etc., complete	C.yds.	0 4 0	44	
2	Lime concrete filling in for foundations 1′ depth well tamped, etc.	C.ft.	0 4 0	396	
3	Size stone in mud foundations and basement with bond stones 6′ apart, etc., complete	,,	0 4 0	823	
4	Burnt stone slabs one line dressed and fixed in mortar	S.ft.	0 12 0	56¼	
5	Burnt brick in mud superstructure	C.ft.	0 3 0	1,258	
6	Burnt brick in mortar	,,	0 4 0	312	
7	Plain cement concrete sills below ventilators and windows (1 : 2 : 4)	,,	0 12 0	9·3	
8	R.C.C. lintels over doors and windows using 1 : 2 : 4 proportions	,,	1 8 0	10·30	
9	Doors with treated seasoned jungle wood, 3½″×4″ frame and 1¼″ battened shutters, including all fixtures, complete	S.ft.	1 2 0	130·0	
10	Windows in treated and seasoned junglewood with 3″×4″ frames and 1″ battened shutters and ¾″ of bars including all fixtures, complete	,,	1 4 0	77	
11	Fixing 41 lbs. rail for ridge	R.ft.	0 8 0	40	
12	Treated and seasoned junglewood wrought and put up	C.ft.	3 0 0	44·07	
13	Roofing with first class Mangalore tiles on treated and seasoned T. W. reapers 2″×1″	Sqr.	22 0 0	10·26	
14	Ridge tiles set in mortar and cement pointed	R.ft.	0 8 0	27	
15	Plastering with lime mortar	Sqr.	3 8 0	33·02	
16	Constructing mortar bands over roof with brick in mortar	R.ft.	0 2 6	70	
17	White washing 2 coats	Sqr.	0 4 0	33	
18	Flooring with 1½″ cement concrete over a bed of stone jelly in lime mortar 3″ thick, plastered with cement mortar ½″ thick rendered smooth, etc., complete	Sqrs.	17 0 0	4·95	
19	Silicate painting to doors and windows	,,	3 8 0	2·07	
20	Cement pointing to basement	,,	3 8 0	1·59	
21	Constructing sinks in bath and kitchen	No.	2 8 0	2	
22	Providing and fixing pestle and mortar	Set	5 0 0	1	
23	Providing a bathroom hearth with chimney	Each	6 0 0	1	
24	Constructing a dhoby seat	L. S.	..	..	
25	Providing and fixing 2 shelf planks 6′ long and 1′ wide	Each	1 8 0	2	
26	Construction of kitchen hearts with two sets	L. S.	..	..	
27	Construction of a masonry latrine in brick in mortar 4½′×4½′ inner dimension 6½′ height	,,	..	..	
28	Providing and fixing outlet pipes 1½″ dia.	No.	0 4 0	7	
29	Clearing site, etc.	L. S.	..	..	
30	Construction of a cowshed	,,	..	..	

Notification dated 30th November 1939.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 3 P.M. on 22nd December 1939, for extending and improving Government Middle School at Tirthahalli, Shimoga District. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1940.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer on a payment of annas four only. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a treasury challan of Rs. 115 as earnest money, and be superscribed "Tender for Extending and Improving Government Middle School at Tirthahalli, Shimoga District," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words, as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. A reserve of 5% on the value of work done will be withheld in Bills towards security deposit.

14. The quantities given in the abstract estimate are only for one room. Two such rooms are to be extended.

Abstract estimate for extending and improving Government Middle School at Tirthahalli, Shimoga District.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
1	Earthwork excavation for foundation and filling in basement including tamping, etc., complete	C.yd.	0 4 0	25	
2	Filling in foundations with lime concrete ..	C.ft.	0 4 0	165	
3	Filling in foundation with size stone in mud including providing bond stones 6′ apart, etc., complete	,,	0 4 0	549	
4	Burnt brick in mud for superstructure ..	,,	0 3 0	1,218	
5	Burnt stone slabs dressed and fixed 4″ to 6″ thick	S.ft.	0 6 0	218	
5a	T. W. doors, $3\frac{1}{2}''\times4\frac{1}{2}''$ frames, $1\frac{1}{4}''$ thick panelled shutters, iron parliamentary hinges, etc., complete	,,	1 8 0	60	
6	T. W. windows, $3\frac{1}{2}''\times4\frac{1}{2}''$ frames, $1\frac{1}{4}''$ thick panelled shutters cut into two halves, etc., including iron bars complete	,,	1 12 0	47	
7	T. W. ventilators with iron bars, brass hinges, bolts and glazed shutters, etc., complete ..	,,	1 0 0	18	
8	Dismantling the old windows including refixing two in the existing rooms and one in the new room including brick work, plastering, etc., complete	No.	3 0 0	3	
9	Dismantling one ventilator and refixing in new wall including plastering, etc., complete ..	,,	2 0 0	1	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
10	Junglewood wrought and put up	C.ft.	2 8 0	35·11	
11	Roofing with 1st class Mangalore tiles on T. W. reepers 2″×1″	Sqr.	22 0 0	5·00	
12	Chunam mortar plastering	,,	3 8 0	17·20	
13	White and colour washing two coats	,,	0 5 0	17·20	
14	Flooring with 4″ surki concrete, 1½″ cement concrete and ¾″ cement plaster cut into 9″ squares, etc., complete	,,	22 0 0	2·27	
15	Cement pointing to basement	,,	4 0 0	1·02	
16	Ridge tiles set in mortar and cement pointed	R.ft.	0 8 0	19	
17	Providing and fixing T. W. Eave boards to the required widths, ¾″ thick	,,	0 8 0	65	
18	Providing and fixing T. W. finials	No.	2 0 0	1	
19	Do Pendents	,,	1 0 0	2	
20	Chocolate painting two coats	Sqr.	3 8 0	5·19	
21	Wood oiling to wood work	,,	2 8 0	3·00	
22	Constructing mortar bands at ends	R.ft.	0 3 0	27	

Notification dated 1st December 1939.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 3 P.M., on 22nd December 1939, for constructing a Primary School building for Adikarnataka colony at Byrapur, Channagiri Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1940.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga, between the hours of 11 A.M. and 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer on payment of annas four only. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a treasury challan for Rs. 70 (seventy) as earnest money and be superscribed "Tender for constructing a Primary School building for Adikarnataka colony at Byrapur, Channagiri Taluk", in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Chamundy brand cement should be used for all cement works.

14. A reserve of 5 per cent on the value of work done will be withheld from bills towards the security deposit.

Abstract estimate for constructing a Primary School Building for Adikarnataka Colony at Byrapur, Channagiri Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
1	Earthwork excavation for foundation and filling in basement, spreading extra carts and including watering and tamping complete ..	C.yd.	0 3 0	17	
2	Stone jelly chunam concrete for foundation and including well tamping complete	C.ft.	0 4 6	121	
3	Size stone in mud for foundation and basement including providing bond stones at every 6′ apart in each course, etc., complete ..	C.ft.	0 4 0	578	
4	Burnt brick in mud for superstructure	„	0 3 6	917	
5	Providing teakwood wrought and put up including wood oiling two coats	„	4 8 0	48·0	
6	Roofing with 1st class Mangalore tiles on T. W. reepers complete	Sqr.	25 0 0	8·34	
7	Ridging with Mangalore ridge tiles in mortar and cement pointing	R.ft.	0 8 0	27¼	
8	Supplying and fixing T. W. doors of the approved design 3½″×4½″ frames with 1¼″ battened shutters and including fixing with necessary hinges, bolts, hooks, padlocks and two coats of chocolate paint, etc., complete	S.ft.	1 4 0	49	
9	Supplying and fixing T. W. windows of the approved design 3½″×4½″ frames with iron bars and battened shutters 1¼″ thick, including fixing with necessary fixtures and two coats of chocolate paint, etc., complete	S.ft.	1 8 0	35	
10	Flooring with Cuddapah slabs or 3″ chunam concrete bed with cement pointing, etc., complete ..	Sqr.	25 0 0	4·5	
11	Supplying and fixing B. S. slabs 6″ thick for pillars, lintels, etc., with grooves and nice dressing, etc., complete	S.ft.	0 8 0	138	
12	Chunam mortar plastering	Sqr.	4 0 0	17¼	
13	White washing two coats	„	0 4 0	17¼	
14	Cement pointing to basement including raking cut joints	„	4 0 0	1·5	
15	Constructing mortar bonds, over roof in brick in mortar and including plastering and white washing, etc., complete	R.ft.	0 2 6	61	
16	Providing T. W. eave board 9″ deep and including two coats of chocolate paint	„	0 8 0	54½	
17	Making a wall board with nice cement plaster in the wall and with black paint, etc., complete ..	L. S.	.. ..	..	
18	Clearing site, levelling ground, etc. ..	„	..	..	

D. A. HUKERI,
Executive Engineer.

ANJANAPUR DIVISION.

Notification dated 2nd December 1939.

Quotations are invited for the purchase of two portable engines of the following description :—

No.	Mys. No.	Make	Condition
1	26	Raboy & Co., Lincoln ..	Not in use for sometime. Requires repairs.
2	115	Clayton & Shuttleworth, Lincoln.	Do do

These are kept in front of the Executive Engineer's Office at Anjanapur and may be examined on any working day. The last date for the receipt of quotations is 25th December 1939.

M. VENKATAKRISHNA RAO,
Executive Engineer.